

### **ADDENDUM NO. 1.0**

# REPLACEMENT OF INDUSTRIAL AVENUE BRIDGE (NO. 025030) OVER UNNAMED STREAM PROJECT Cheshire, Connecticut

SLR #141.11047.00059 Original Bid Package Issued January 30, 2024 Addendum No. 1 Issued February 8, 2024

This Addendum No. 1 includes clarifications and modifications to the above-referenced bid package. Changes reflected herein shall supersede all previous bid package documentation.

#### A. PRE-BID MEETING DESCRIPTION OF PROJECT

The proposed work for this project includes the removal of the existing twin pipes and headwalls on Industrial Avenue and replacement with a three-sided concrete box culvert. Work also includes installation of water main hangers. Installation of wingwalls, full-depth reconstruction of Industrial Avenue, and other work as identified on the plans and detailed herein. The scope includes but is not limited to the following:

- a. Installation of Detour and roadway closure, and maintenance during length of construction. Note contractor to maintain driveway access of minimum 15'.
- b. Installation of Sedimentation & Erosion Controls
- c. Installation of temporary water handling cofferdams
- d. Installation of bridge and wingwall footings, channel features, and channel grading
- e. Installation of culvert and remaining channel features
- f. Installation of roadway drainage, water main hangers, concrete parapets.
- g. Full-depth roadway, driveways, railings, plantings, grading, and turf establishment
- h. Removal of all temporary features
- i. Restore Site

#### **B. CLARIFICATIONS**

- Materials testing and laboratory cost shall be incurred by the contractor per Item 1 "Mobilization and Demobilization".
- The specifications call for Construction Field Office, this is not a requirement for the Town of Cheshire the contractor may leave the Item 3 "Construction Field Office" blank on Schedule of Items.
- The contractor has 90 calendar days from start of construction to complete the contract work, including opening the roadway. Liquidated damages are \$1000 per calendar day.

#### Attachments

## PRE-BID MEETING SIGN-IN SHEET

**Meeting Date:** 

February 6, 2024

Project:

Replacement of Industrial Avenue over Unnamed Stream (Bridge No. 025030)

Place:

Industrial Avenue Cheshire, CT

Name	Company	Phone	E-Mail
Peter Jeslei	New England Infrastructure	860-4716561	Presicioneintrosimetre, con
Willie Fritz	Arborio Corp	860-234-4341	chaldiearborioca
Justin Stone	Town of Cheshire	203 2716650	Istone @ cheshinect-ore
PHIL STRAKER	Tam of Cotestiet	203 271 6650	pstraker & cheshired
LUKE STAMOUR	HEMLUCK CONST	860-442-750	pstraker & cheshired henlock const g e gmain. con
Norm Nagy	Nagy Bros Const	2032680454	nagbrocalcom
Kisitor Patel	5LR	203-271-1773	kpatel@slrconsulting.
NIRDOSH PATER	SCR	425 - 548 - 0272	npatel @ SUN consulting.
	*		
		2	-